



Blue Coat School, Coventry

Contract Details - Education

Value: £3.5 m
 Start Date: 9th July 2007
 Completion Date: 22nd December 2008
 Duration: 76 weeks

Client: Blue Coat School
 Architect: Viner Associates
 Quantity Surveyor: Y M D Boon

Contract Description

- 3 storey arts centre comprising of a planar glazing atrium entrance, auditorium to seat 750 people, orchestra pit, classrooms, studios, changing facilities, cloakrooms and a bridge link connecting the new facility to the existing 6th Form centre at second floor.
- Steel frame with precast floors and stairs and external insulated panels fixed to a metal stud framing.
- Insulated acoustic roof panels with a tiled roof.
- Underpinning to adjacent building.
- Theatre completed in rough textured blocks with a wood floor.
- Two full height acoustic sliding panels provided to the theatre enabling it to be split into two.

Key Features

- Working inside a live school environment.
- Restricted access and delivery times.
- Planar glazing to entrance.
- Retractable seating to hall.
- Acoustic curved ceiling to atrium.
- Stage lighting and sound system by Stage Electrics.
- Gantry to accommodate stage lighting.